



## MCA DEPARTMENT OF ECONOMIC DEVELOPMENT — REQUEST FOR QUOTES (RFQ)

### Modification, Upgrading, & Paving of A'nowara:kowa Arena Walking Trail

36 Arena Road  
Akwesasne, Ontario K6H 5R7

---

**QUOTES ARE DUE AT 2:00 PM ON OCTOBER 31, 2022**

---

**RESPONDING TO THIS REQUEST FOR QUOTE.** Quotes may be hand-delivered to the MCA Department of Economic Development Office, 167 International Road, Unit #3 between the hours of 8- 4 Monday to Friday. Emailed quotes will be accepted if they are emailed to [ec.dev@akwesasne.ca](mailto:ec.dev@akwesasne.ca), received by the deadline stated above. Please provide in detail and itemize price of materials and services provided for project.

**SCOPE OF WORK.** The Contractor shall provide all labor, equipment, materials and perform all work as shown on the attached drawing and list the scope of work. All work shall be in accordance with construction standards.

**COMPLETION TIME FOR THE WORK.** The Contractor is encouraged to complete work as soon as possible (November 18, 2022).

**SITE INSPECTION.** Bidders are encouraged to visit the Project sites prior to submitting a quote for this Work. Contact Mark Martin (613-936-1583 or [mark.martin@akwesasne.ca](mailto:mark.martin@akwesasne.ca)) for site visit(s) and/or questions.

**QUALITY OF WORK.** All Work shall conform to the drawings and specifications, industry standards and practices, and the manufacturer's requirements. The Contractor shall be responsible for the supervision and control of all Work; the safety of the workers; and assurance that the quality of Work and character of workers conform to all applicable laws and regulations.

**QUALIFICATIONS.** Interested parties must demonstrate:

- An understanding of and compliance with MCA Construction and Safety Guidelines
- For General Contractor confirmation of bonding is required
- Ability to procure and maintain "All Risk and Liability Insurance (\$2M Minimum)" in accordance with General Conditions
- Be able to furnish clearance from Workers Safety and Insurance Board (WSIB) or (CSST)



**DELIVERABLES.** The Contractor shall provide a completed “As-Built” drawings and all other related documents, both hard copy and digital file to the MCA upon completion of the project.

## **SCOPE OF WORK.**

- Expanding width of trail along North side of playground and skatepark heading west. Remove topsoil/material 12" down, lay fabric, lay 8" granular A and 3-4" gravel dust, level and tamp (TO BE PAVED). Trail will be 10' wide and 230-foot length.
- Modify the North-east portion of the trail 35' from (point A) to (point B) which is 79' from the trail and approximately 408' in length.
- Modifications and Redirect trail from west side of the playground towards river edge of trail, 175' - from (point C) towards existing trail to alongside block one boundary area (point D). In addition, from this (point D) a new trail will head west 100' (point E) and then 64' North to existing trail. Remove topsoil/material 12" down, lay fabric, lay 10" granular A and 3-4" gravel dust, level and tamped (TO BE PAVED). Trail will be 6' wide.
- Clear construction materials and garbage in the construction area. There is a trash on the south side of the arena.
- Repair existing walking trail and ensure proper banking is constructed for paving. May need to replace troubled areas of walking trail to ensure proper paving.
- Paving the existing 3545 linear feet walking trail with the width of 6' and a small area of 10'. Minimum 4" of Asphalt shall be installed to ensure small utility use during maintenance.