



MCA DEPARTMENT OF ECONOMIC DEVELOPMENT — REQUEST FOR QUOTES (RFQ)

Modification, Upgrading, & Paving of Kana:takon Recreation Walking Trail

16 Park Street
Akwesasne, Quebec H0M 1A0

QUOTES ARE DUE AT 2:00 PM ON DECEMBER 9, 2022

RESPONDING TO THIS REQUEST FOR QUOTE. Quotes may be hand-delivered to the MCA Department of Economic Development Office, 167 International Road, Unit #3 between the hours of 8 a.m. – 4 p.m. Monday to Friday. Emailed quotes will be accepted if they are emailed to ecdev@akwesasne.ca, received by the deadline stated above. Please provide in detail and itemize price of materials and services provided for project.

SCOPE OF WORK. The Contractor shall provide all labor, equipment, materials and perform all work as shown on the attached drawing and list the scope of work. All work shall be in accordance with construction standards.

COMPLETION TIME FOR THE WORK. The Contractor is encouraged to complete work as soon as possible in the Spring of 2023.

SITE INSPECTION. Bidders are encouraged to visit the Project sites prior to submitting a quote for this Work. Contact Troy Thompson at 613-575-2250 ext. 1803 or troy.thompson@akwesasne.ca for site visit(s) and/or questions.

QUALITY OF WORK. All Work shall conform to the drawings and specifications, industry standards and practices, and the manufacturer's requirements. The Contractor shall be responsible for the supervision and control of all Work; the safety of the workers; and assurance that the quality of Work and character of workers conform to all applicable laws and regulations.

QUALIFICATIONS. Interested parties must demonstrate:

- An understanding of and compliance with MCA Construction and Safety Guidelines
- For General Contractor confirmation of bonding is required
- Ability to procure and maintain "All Risk and Liability Insurance (\$2M Minimum)" in accordance with General Conditions
- Be able to furnish clearance from Workers Safety and Insurance Board (WSIB) or (CSST)



DELIVERABLES. The Contractor shall provide a completed “As-Built” drawings and all other related documents, both hard copy and digital file to the MCA upon completion of the project.

SCOPE OF WORK (PLEASE SEE ATTACHED DRAWING).

- Expand from existing trail on west side of property, heading south and around lacrosse box, and heading back to the existing trail (in between the lacrosse box and pavilion). Remove topsoil/material 12" down, lay fabric, lay 8" granular A and 3-4" gravel dust, level and tamp (TO BE PAVED). Trail will be 8' wide and 1,100' long.
- Expand from the existing trail on west side of property to the existing sidewalk at sweet grass manor (heading west). Remove topsoil/material 12" down, lay fabric, lay 10" granular A and 3-4" gravel dust, level and tamped (TO BE PAVED). Trail will be 8' wide.
- Expand from existing trail on the east side of the property by adding a tear shaped turn around. Remove topsoil/material 12" down, lay fabric, lay 8" granular A and 3-4" gravel dust, level and tamp (TO BE PAVED). The turn around measures 15' wide and 20' long.
- Minimum 4" of Asphalt shall be installed to ensure small utility use during maintenance.

